Bridgeport Milling Machine – Drive System Analysis

Serial Number: 288690978U

Student Name: Callum Bartaby

Date: 20th November 2025

Tutor Name: Jim Chuter

Date:

Bracknell College

Engineering

T Level Engineering 2025–27

Assignment Task: Technical Report – Bridgeport Drive System

This assignment requires the following to be completed:

1. Technical description of the existing Bridgeport Milling Machine drive system (top-mounted assembly).

2. Identification of key components and their functions.

3. Consideration of alternative drive components or upgrade paths.

Procedure Sheet – Bridgeport Milling Machine Drive System Analysis

1. Procedure

1. Obtain all relevant documentation before starting work.

2. Ensure the milling machine is isolated from power and safely locked off.

3. Visually inspect the top-mounted drive housing for damage, leaks, or loose components.

4. Document all existing drive system components, including motor, pulleys, belts, gears, and speed-change mechanisms.

5. Record nameplates or markings on major components (motor, gear housing, vari-speed assembly).

6. Take photographs or sketches to support analysis where permitted.

7. Compare identified components to standard Bridgeport configurations to confirm model and variations.

8. Evaluate condition of belts, bearings, and motor based on visible wear.

9. Note any unusual noises, vibration, or resistance when manually rotating the spindle (machine unpowered).

10. Prepare findings for the technical write-up.

2. Tools and Equipment

• Allen keys and spanners

• Ruler or calipers

• Notebook and pen

• PPE: safety glasses, gloves, steel-toe boots

3. Hazards and Controls

• Electrical hazard –Ensure the machine is isolated and locked off.

• Moving components –Confirm no power source is connected; avoid rotating components during inspection.

• Oil/grease contamination – Wear suitable gloves and maintain stable footing.

• Sharp edges – Handle sheet-metal covers and internal parts carefully.

Bridgeport Milling Machine – Drive System Technical Report

Serial Number: 288690978U

1. Existing Drive System Overview

• The Bridgeport milling machine uses a top-mounted drive system designed to provide variable spindle speed and reliable torque.

• Most Bridgeport models utilise a combination of an electric motor, pulley system, and variable-speed mechanism.

• The drive assembly transmits motion from the motor down to the spindle through belts and a quill assembly.

2.1 Main Drive Components

• Electric Motor – Typically a 1–2 HP single or three-phase motor mounted at the top rear.

• Variable Speed (Vari-Speed) Pulley Assembly – Expanding/contracting pulleys allowing adjustable spindle speeds.

• V-Belt / Timing Belt – Transfers power from motor pulley to drive pulley.

• Back-Gear Assembly – Allows switching between high-speed and high-torque modes.

• Spindle Quill & Drive Shaft – Transmits rotary motion to cutting tools.

2.2 Mechanical Operation Summary

Power from the motor rotates the upper pulley assembly. Depending on speed selection, the Vari-speed mechanism adjusts belt tension and pulley diameter, allowing smooth transitions. The lower drive pulley turns the spindle assembly through the quill shaft. Back-gear mode enables a slower spindle range suitable for heavy cuts.

3. Condition Considerations

• Inspect belt wear, cracks, or glazing.

• Check motor bearings for noise or play.

• Verify Vari-speed bushings and keys for wear.

• Ensure pulleys have no side-to-side wobble.

4. Recommended Upgrade Options

• Replace old motor with a modern inverter-rated motor for VFD control.

• Install a Variable Frequency Drive (VFD) to gain smoother speed control and torque at low RPM.

• Upgrade belts to modern high-strength timing belts.

• Replace worn vari-speed bushings, keys, and pulley bearings.

• Install improved spindle bearings for reduced vibration.

5. Conclusion

The top-mounted Bridgeport drive system is robust but may suffer wear with age. Proper inspection and targeted upgrades such as a VFD system, new belts, and refreshed mechanical components can significantly extend machine life and improve precision.

Bridgeport Milling Machine Job Report

Serial Number: 288690978U

I started by creating a safe workspace by ensuring a cautionary cordon was established to ensure technician safety. After validating the cordon, one of the crew members isolated the power by the mains via padlocking the control switch.

Once we ensured total safety in the workspace, one technician started by unbolting the main bolts securing the motor housing to the top pulley housing. This was completed using a 9/16 AF open ended spanner. We then carefully removed the motor from the machine and placed it on the floor. One of our members unfortunately dropped the motor and the electrical housing was destroyed causing the entire electrics system for the motor to be removed.

Once the motor was securely off the machine, we removed the three smaller bolts securing the pulley system housing to the machine using a ½ AF open ended spanner and used an Allen key to remove the 6 Allen screws from the underside of the cover. The cover was then removed and safely set aside as well as the retaining collar.

The Vee-Belt was removed and inspected. Upon inspection we did not notice any major faults but did notice some wear from usage. Due to the lack of damage, we re-installed the same belt, attached the pulley cover and re-screwed the Allen screws into the underside of the cover. The top bolts of the cover were then attached and secured. The retaining collar was reinstalled, and the motor was placed into its designated slot. The motor was then

bolted down safely and securely, and the dust covers were replaced. Finally, we removed the padlock from the power source and dismantled the safety cordon.

Procedural Photos:

Isolation of power:



Removal Of Dust Covers:

Removal of Motor Bolts:

Removal of motor and pulley cover:

Removal of vee-belt:



Full Re-assembly:

FORMATTED BY CHATGPT